

Lawrence Berkeley National Laboratory

Recent Work

Title

Status of the DARHT phase 2 long-pulse accelerator

Permalink

<https://escholarship.org/uc/item/70r579n6>

Authors

Burns, M.J.
Carlsten, B.E.
Davis, H.A.
[et al.](#)

Publication Date

2001-02-01

STATUS OF THE DARHT PHASE 2 LONG-PULSE ACCELERATOR*

M.J. Burns, B.E. Carlsten, H.A. Davis, C.A. Ekdahl, B.T. McCuistian, F.E. Merrill,
K.E. Nielson, C.A. Wilkinson
Los Alamos National Laboratory, P.O. Box 1663, Los Alamos, NM 87544

K.P. Chow, H.L. Rutkowski, W.L. Waldron, S.S. Yu
E.O. Lawrence Berkeley National Laboratory, 1 Cyclotron Rd., Berkeley, CA 94720

G.J. Caporaso, Y.J. Chen, S. Sampayan, J.A. Watson
Lawrence Livermore National Laboratory, 7000 East Ave., Livermore, CA 94550

The Dual-Axis Radiographic Hydrodynamics Test (DARHT) facility will employ two perpendicular electron Linear Induction Accelerators to produce intense, bremsstrahlung x-ray pulses for flash radiography. We intend to produce measurements containing three-dimensional information with sub-millimeter spatial resolution of the interior features of very dense, explosively-driven objects. The facility will be completed in two phases with the first phase having become operational in July 1999 utilizing a single-pulse, 20-MeV, 2-kA, 60-ns accelerator, a high-resolution electro-optical x-ray imaging system, and other hydrodynamics testing systems. The second phase will be operational in 2003 and features the addition of a 20-MeV, 2-kA, 2-microsecond accelerator. Four short electron micropulses of variable pulse-width and spacing will be chopped out of the original, long accelerator pulse for producing time-resolved x-ray images. The second phase also features an extended, high-resolution electro-optical x-ray system with a framing speed of about 2-MHz. Production of the first beam from the Phase 2 injector will occur this year. In this paper we will present the overall design of the Phase 2 long-pulse injector and accelerator as well as some component test results. We will also discuss the downstream transport section that contains the fast kicker used to separate the long-pulse beam into short bursts suitable for radiography as well as the x-ray conversion target assembly. Selected experimental results from this area of the project will also be included. Finally, we will discuss our commissioning plans and diagnostics.

* Work supported by the U.S. Department of Energy under contracts W-7405-Eng-36 (LANL), DE-AC03-76SF00098 (LBNL), and W-7405-Eng-48 (LLNL).